

BRUHAT BENGALURU MAHANAGARA PALIKE
YELAHANKA ZONE

OF WORK : Improvements to CC road and drain kogilu main road to Anjeneya temple road in kempegowda ward no-01

Estimate Cost Rs.							15.00	Lakhs
Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
SRB 2-2.1 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 SR 2018-19 ✓								
	Cum							
for CC road		1	54.00	3.50	0.275	51.98 ✓		
		1	100.00	4.50	0.275	123.75 ✓		
		1	60.00	3.50	0.275	57.75 ✓		
						233.48 ✓	316.94	73998.00 ✓
Basic Rate Rs	299.00 ✓							
Add Area Weightage @ 6%	17.94 ✓							
Total	316.94 ✓							
KSRB4.1.3: Providing and laying position plain cement concrete of Mix 1:4:8 with OPC cement @180Kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15 cms, thick, well compacted, in foundation, including cost of all materials, Labour, HOM of Machinery, Curing complete as per Specifications. Specifications No. KBS 4.1, 4.2 (P12/4.3). SR 2018-19								
for cc road		1	54.00	3.50	0.15	28.35 ✓		
		1	100.00	4.50	0.15	67.50 ✓		
		1	60.00	3.50	0.15	31.50 ✓		
						127.35 ✓	5408.12	688724.00 ✓
Basic Rate	5102.00 ✓							
Area Weightage @ 6%	306.12 ✓							
Total	5408.12 ✓							
3 KSRRB M600-6: cement concrete pavement, construction unreinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with 43 grade cement or any other type as per clause 1051.2.2M20/M30 at 380/450 kg per cum, coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25mm, mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including leveling the form work as per drawing.), spreading the concrete with shovels, rakers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved curing compound, finishing to lines and grade as per drawing complete as per specification M30(at 360kg per cum coarse aggregate @ 0.69cum and fine aggregate @ 0.46cum), , No. 174/ Item No. 22.6.1) SR 2018-19								
	Cum							
for cc road		1	54.00	3.50	0.125	23.63 ✓		
		1	100.00	4.50	0.125	56.25 ✓		
		1	60.00	3.50	0.125	26.25 ✓		
						106.13 ✓	5210.96	553039.00 ✓
Basic Rate	4916.00 ✓							
Area Weightage @ 6%	294.96 ✓							
Total	5210.96 ✓							

Description of Item	Unit	No.	L	B	D	Qty.	Rate	Amount
RB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/								
from KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping,								
ing for return trip, excluding time for haulage and return trip complete as per specifications								
RTH -100/ Chapter 1 (Page No.136 Item No 17.1) SR 2018-19								
	Cum					233.48	87.56	20442.00
						Qty Vide Item No.1		
Basic Rate for loading and unloading	57.00							
Basic Rate for Haulage upto 8.00 k.m	25.60							
28 X 2.50 X 8								
Basic Rate	82.60							
Area Weightage 6%	4.96							
Grand Total	87.56							
						Sub total		1336177.00
								160341.24
GST of 12% as per Govt Letter No PWD 65 RDF 2017 Dated 11-10-2018								
								160341.24
								3481.76
Miscellaneous and unforeseen charges	Ls							3481.76
						Total Ammount Rs.		1500000.00
(Rupees F lakhs only)								

FICATE

The site has been inspected and the work is found to be necessary.
The rates adopted are as per PW,P IWTD SR of 2018-19
The provisions were made in this estimate are necessary and adequate.
The area comes under the Bruhat Bengaluru Mahanagara Palike Limits.
This work is not repeated in any other programs or Grants

Assistant Engineer
Ward No.1

Executive Engineer
Yelahanka-Division
B.B.M.P

Assistant Executive Engineer
Yelahanka Sub-Division
B.B.M.P

Administrative Approval

Accorded For Rs. 15.00 Lakhs only
Head of A/C. P.1771
CER NO : 19.1 Dt: 25.02.19

TA

CE (YNK)

TECHNICALLY SANCTIONED FOR Rs. 15.00 Lakhs
Rupees Fifteen Lakhs only
Under P.1771 - 2018-19
Registered as CE () No. 9 9
Subject to conditions contained in
enclosed memo EE () No. /9/
Dt. Estimate A/ Sanctioned
EE/TE/32/2018-19 No.
Dated 25.2.19 Rs. 15.00 Lakhs

Executive Engineer

[illegible]

[Signature]

 PROPOSED WARD BOUNDARY
 RIVER/ DRAIN
 RAILWAY LINE
 ROAD